# BRUHAT BANGALORE MAHANAGARA PALIKE

## YELAHANKA ZONE

**Name of work:** Detailed Estimate for the Work of Improvements to Road and Drains at Venkateshpura nagara main Road and Cross Roads in ward No 05 Byatarayanapura Sub Division

| | | | Estimate Cost | | | | | | 3000000.00 |
|---|---|---|---|---|---|---|---|---|---|
| Sl No | Description of item | Unit | No | L | B | D | Qty | Rate | Amount |
| 1 | KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No KBS 2.1(a) / 2.3.1,P. No. 5/ Item No. 2.1/ PWD SR 2013-14 | cum | | | | | | | |
| | **For Road Surface** | | | | | | | | |
| | 4th and 5th Cross | | 2 | 240.00 | 5.50 | 0.20 | 528.00 | | |
| | 2nd Main | | 1 | 220.00 | 5.50 | 0.20 | 242.00 | | |
| | **Desilting of Drains** | | | | | | | | |
| | 4th and 5th Cross | | 2X2 | 240.00 | 0.35 | 0.20 | 67.20 | | |
| | 2nd Main | | 1X2 | 220.00 | 0.35 | 0.20 | 30.80 | | |
| | **Burm Cutting** | | | | | | | | |
| | 4th and 5th Cross | | 4 | 240.00 | 0.95 | 0.20 | 182.40 | | |
| | 2nd Main | | 2 | 220.00 | 0.95 | 0.20 | 83.60 | | |
| | | | | | | | **1134.00** | 126.36 | **143292.00** |
| | Basic Rate | 117.00 | | | | | | | |
| | Area Weightage @ 8% | 9.36 | | | | | | | |
| | **Total** | **126.36** | | | | | | | |
| 2 | KSRRB 300-1. Earth work excavation by manual means in **hard soil** involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.MORTH chapter 3. No. 152/ Item No. 19.2/ PWD SR 2013-14 | cum | | | | | | | |
| | For Culverts | | 5 | 6.20 | 1.85 | 1.05 | 60.22 | | |
| | | | | | | | **60.22** | 90.72 | **5463.00** |
| | Basic Rate | 84.00 | | | | | | | |
| | Area Weightage @ 8% | 6.72 | | | | | | | |
| | **Total** | **90.72** | | | | | | | |
| 3 | Removing B.S Slab of Drain and stacking Page No. 28/ Item No. 5.32/ PWD SR 20113-14 | Sqm | | | | | | | |
| | 4th and 5th Cross | | 2X2 | 240.00 | 1.65 | | 1584.00 | | |
| | 2nd Main | | 1X2 | 220.00 | 1.65 | | 726.00 | | |
| | | | | | | | **2310.00** | | |
| | **Deduct 30% Missing Slabs** | | | | | | 693.00 | | |
| | | | | | | | **1617.00** | 50.11 | **81031.00** |
| | Basic Rate | 46.40 | | | | | | | |
| | Area Weightage @ 8% | 3.71 | | | | | | | |

| Sl No | Description of item | Unit | No | L | B | D | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|
| | Total | **50.11** | | | | | | | |
| 4 | Refixing stone slabs of drains and pointing in C.M (1:3) Page No. 28/ Item No. 5.33/ PWD SR 2013-14 | Sqm | | | | | | | |
| | | | Qty Vide Item No.3 | | | | 1617.00 | | |
| | | | | | | | **1617.00** | **70.04** | **113251.00** |
| | Basic Rate | 64.85 | | | | | | | |
| | Area Weightage @ 8% | 5.19 | | | | | | | |
| | Total | **70.04** | | | | | | | |
| 5 | Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete -do- 7.5 cms thick Page No. 28/ Item No. 5.31.1/ PWD SR 2013-14 | **Sqm** | | | | | | | |
| | **For Missing slabs (30%)** | | Missing Slabs | | | | 693.00 | | |
| | | | | | | | **693.00** | 343.44 | **238004.00** |
| | Basic Rate | 318.00 | | | | | | | |
| | Area Weightage @ 8% | 25.44 | | | | | | | |
| | **Total** | **343.44** | | | | | | | |
| 6 | KSRB-4-1.3 : Providing and laying in position **plain cement concrete of mix M 7.5** withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2013-14 | **Cum** | | | | | | | |
| | For Culverts | | 5 | 6.20 | 1.85 | 0.15 | 8.60 | | |
| | | | | | | | **8.60** | 4290.84 | **36912.00** |
| | Basic Rate | 3973.00 | | | | | | | |
| | Area Weightage @ 8% | 317.84 | | | | | | | |
| | Total | **4290.84** | | | | | | | |
| 7 | KSRB 5.2.3 Providing and constructing granite / trap / basalt Size stone masonry **in foundation** with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 Page No. 25/ Item No. 5.6/ PWD SR 2013-14 | cum | | | | | | | |
| | For Culverts | | 5X2 | 6.20 | 0.60 | 0.45 | 16.74 | | |
| | | | | | | | **16.74** | 3549.96 | **59426.00** |
| | Basic Rate | 3287.00 | | | | | | | |
| | Area Weightage @ 8% | 262.96 | | | | | | | |
| | **Total** | **3549.96** | | | | | | | |

| Sl No | Description of item | Unit | No | L | B | D | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|
| 8 | KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry **in basement** with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 26/ Item No. 5.9/ PWD SR 2013-14 | **Sqm** | | | | | | | |
| | For Culverts | | 5.X2 | 6.20 | 0.50 | 0.45 | 13.95 | | |
| | | | | | | | **13.95** | **4227.12** | **58968.00** |
| | Basic Rate | 3914.00 | | | | | | | |
| | Area Weightage @ 8% | 313.12 | | | | | | | |
| | **Total** | **4227.12** | | | | | | | |
| 9 | KSRB 4-6.7 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1 m in depth including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 17/ Item No. 4.34/ PWD SR 2013-14 | **Sqm** | | | | | | | |
| | For Culverts | | 5 | 6.20 | 0.60 | | 18.60 | | |
| | For Sides | | 5X2 | 6.20 | 0.23 | | 14.26 | | |
| | | | 5X2 | 1.65 | 0.23 | | 3.80 | | |
| | | | | | | | **36.66** | **244.08** | **8947.00** |
| | **Basic Rate** | **226.00** | | | | | | | |
| | Area Weightage @ 8% | 18.08 | | | | | | | |
| | **Total** | **244.08** | | | | | | | |
| 10 | KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix **M10** withOPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1.4.2/P No. 13/ Item No. 4.7/ PWD SR 2013-14 | **cum** | | | | | | | |
| | For Culverts | | 5X2 | 6.20 | 0.45 | 0.10 | 3.35 | | |
| | Vent Bed | | 5 | 6.20 | 0.60 | 0.10 | 1.86 | | |
| | | | | | | | **5.21** | 4737.96 | **24675.00** |
| | Basic Rate | 4387.00 | | | | | | | |
| | Area Weightage @ 8% | 350.96 | | | | | | | |
| | Total | **4737.96** | | | | | | | |

| Sl No | Description of item | Unit | No | L | B | D | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|
| 11 | KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix **M20** withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6, **No. KBS 4.1,4.6, No. 13/ Item No. 4.11/ PWD SR 2013-14** | **Cum** | | | | | | | |
| | For Culverts | | 5 | 6.20 | 1.65 | 0.23 | 11.76 | | |
| | | | | | | | **11.76** | 5639.76 | **66349.00** |
| | Basic Rate | 5222.00 | | | | | | | |
| | Area Weightage @ 8% | 417.76 | | | | | | | |
| | **Total** | **5639.76** | | | | | | | |
| 12 | KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3 Page No. 19/ Item No. 4.46.1/ PWD SR 2013-14 | **Qtl** | | | | | | | |
| | 0.95 Qtl/Cum | | 0.95 | 11.76 | | | **11.18** | 7380.72 | **82489.00** |
| | Basic Rate | 6834.00 | | | | | | | |
| | Area Weightage @ 8% | 546.72 | | | | | | | |
| | Total | **7380.72** | | | | | | | |
| 13 | KSRB 15.1.3: Providing **FLush pointing** to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 122/ Item No. 15.1/ PWD SR 2013-14 | Sqm | | | | | | | |
| | For Culverts | | 6X2 | 7.00 | | 0.85 | 71.40 | | |
| | | | | | | | **71.40** | 79.92 | **5706.00** |
| | Basic Rate | 74.00 | | | | | | | |
| | Area Weightage @ 8% | 5.92 | | | | | | | |
| | **Total** | **79.92** | | | | | | | |

| Sl No | Description of item | Unit | No | L | B | D | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|
| 14 | KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to **wet mix macadam** specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH specification NO. 406, No. 170/ Item No. 20.18/ PWD SR 2013-14 | Cum | | | | | | | |
| | 4th and 5th Cross | | 2 | 240.00 | 5.50 | 0.15 | 396.00 | | |
| | 2nd Main | | 1 | 220.00 | 5.50 | 0.15 | 181.50 | | |
| | | | | | | | **577.50** | 1121.04 | **647401.00** |
| | Basic Rate | 1038.00 | | | | | | | |
| | Area Weightage @ 8% | 83.04 | | | | | | | |
| | **Total** | **1121.04** | | | | | | | |
| 15 | KSRRB 500-4: providing and applying **primer coat** from 7.5 to 9.8 kg and 9.8 to 12.2kg per 10 sqm for surfaces of low and medium porosity respectively over prepared surface of granular base with cut bank M.C-70 or any other bitumen mixed with diesel at 10 kg per 10 sqm heated in bitumen boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specificationsDo- Medium Porosity MORTH chapter 5, No. 175/ Item No. 21.4/ PWD SR 2013-14 | Sqm | | | | | | | |
| | 4th and 5th Cross | | 2 | 240.00 | 5.50 | | 2640.00 | | |
| | 2nd Main | | 1 | 220.00 | 5.50 | | 1210.00 | | |
| | | | | | | | **3850.00** | 100.60 | **387318.00** |
| | Basic Rate | 93.15 | | | | | | | |
| | Area Weightage @ 8% | 7.45 | | | | | | | |
| | Total | **100.60** | | | | | | | |
| 16 | KSRRB M500-18: Providing and laying **semi dense bituminous concrete 25mm thick** with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specifications. P. No. 174/ Item No. 21.20/ PWD SR 2013-14 | Cum | | | | | | | |
| | 4th and 5th Cross | | 2 | 240.00 | 5.50 | 0.025 | 66.00 | | |
| | 2nd Main | | 1 | 220.00 | 5.50 | 0.025 | 30.25 | | |
| | | | | | | | **96.25** | 9631.44 | **927026.00** |
| | Basic Rate | 8918.00 | | | | | | | |

| Sl No | Description of item | Unit | No | L | B | D | Qty | Rate | Amount |
|---|---|---|---|---|---|---|---|---|---|
| | Area Weightage @ 8% | 713.44 | | | | | | | |
| | Total | **9631.44** | | | | | | | |
| | Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km ( Page No.123, | Cum | | | | | | | |
| | | | Qty. Vide Item No. 1 | | | | **1194.22** | | |
| | | | | | | | **1194.22** | 67.32 | **80395.00** |
| | Basic Rate Lead Charges Upto 2.00 Kms | 5.12 | | | | | | | |
| | PWD SR 2010-11 (P.118/I.17.1) For loading | 62.20 | | | | | | | |
| | **Total** | **67.32** | | | | | | | |
| | | | | | | | | | |
| 18 | For 1% Third Party Charges | | | | | | | | **30000.00** |
| | | | | | | | | | |
| 19 | Miscesallaneous Charges | L/S | | | | | | | **3347.00** |
| | | | | | | | | Total | **3000000.00** |

**(RupeesThirty Laksh Only)**

CERTIFICATE

1 The work spot has been inspected and the work is found necessary.
2 This estimate is prepared as per PWD SR of 2013-14
3 The provisions were made in this estimate are necessary and adequate.
4 This works come under B.B.M.P. limits.

Assistant Engineer
ಸಹಾಯಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ. ಬ್ಯಾಟರಾಯನಪುರ ಉಪ ವಿಭಾಗ

ಸಹಾಯಕ ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ಉಪ ವಿಭಾಗ
ಬಿಬಿಎಂಪಿ, ಬೆಂಗಳೂರು-24
Assistant Executive Engineer

Executive Engineer
Byatarayanapura Division
Bruhat Bangalore Mahanagara Palike

ADMINISTRATIVELY SANCTIONED FOR Rs 30,00
Rupees Thirty Lakh.

Under 110. Village Boards.

Registered as EE ( ) No 9
Subject to conditions contained in
enclosed memo EE ( ) No 01
Dt Estimate Mentioned
ADD. Cont(x) AS No 588/13-14
dated 23-12-13 Rs 30,00

ಜಂಟಿ ಆಯುಕ್ತರು
Joint Commissioner
(Yeshwanthapura Zone)
BBMP, Bengaluru-92.
ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ಬ್ಯಾಟರಾಯನಪುರ, ಬೆಂಗಳೂರು-92

Technical Sanction for Rs. 30-00 Lakhs
Thirty Laks only

Registered as EE No: 80/13-14 Dated Subject
conditions contained enclosed memo.
80/13-14 Dt. 23.12.13

Superintendent Engineer
EE (BTP.Div.)